

BRUHAT BANGALORE MAHANAGARA PALIKEYelahanka Zone, Electrical Division


Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule B"

Name of Work:- Maintenance & Repairs to installation of Existing Park Lightings Panel boards and metering in Yelahanka Constituency in Ward no 04.

Sl. No	Qty	Description Of Work	Unit	Quoted Rates	
				In figures	In words
1	10	Transporting and erecting of 3.5 Mtrs long Swged Tubel or park poles including Digging of pit 45x45x100cms & providing 1:2:4 concrete of size 35x35x130 cms Including coping as per the detaild enclosed civil estimate & drawing	Nos	729.00	Rupees Seven Hundred Twenty Nine Only
2	380	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanised, steel wire/steel tap armoured cable with PVC outer sheathing 1.1 KV class.I. Class 'A' PVC Cable. 4 core 16 sqmm	Mtrs	105.30	Rupees One Hundred Five And Paise Thirty Only
3	380	Labour charges for laying of 1.1 KV class UG cable when supplied agency in existing trench GI pipe / stoneware pipe / on wall /on pole as required. I. In existing trench/duct. 6 sqmm to 16 sqmm	Mtrs	8.10	Rupees Eight And Paise Ten Only
4	350	Digging of trench of 0.6 m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc.,complete. (As perCivil SR KSRB I-2, P-7).a) In soil (ordinary)	Mtrs	58.50	Rupees Fifty Eight And Paise Fifty Only
5	200	Wiring for lighting/power circuit using one of PVC insulated 1100v grade, multis and Copper conductor single core cable in open or consealed system of wiring.I Group A Materials.b)1.5	Mtrs	11.92	Rupees Eleven And Paise Ninety Two Only
6	6	Supply and fixing of 4-pole power contactor with NO/NC contacts on existing wood / panel board using necessary bolts, nuts, washers and wiring etc., complete. d) 100-125 Amps	Nos	7436.25	Rupees Seven Thousand Four Hundred Thirty Six And Paise Twenty
7	12	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and Complete wiring as required confirming IEC 60898. 6) 40-63 Amps TPN	Nos	1452.00	Rupees One Thousand Four Hundred Fifty Two Only
8	59	Wiring for lighting/power circuit using one of PVC insulated 1100v grade, multis and Copper conductor single core cable in open or consealed system of wiring.I Group A Materials.g)16	Mtrs	99.00	Rupees Ninety Nine Only
9	50	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. And M.S. flat... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. a)40X40X6mm	Mtrs	197.25	Rupees One Hundred Ninety Seven And Paise Twenty Five Only
10	175000	Fabricating supplying and mounting MS box made out... SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size cdlamps with mecessary cable entry pipe with gland and box should be finished with 2 cdoats of red oxide primer paint and finally finished with approved colour enameled metal pain etc., complete. b)16 swg	Sqcm	0.25	Rupees And Paise Twenty Five Only

For MEGHANA ELECTRICALS




Proprietor



11	6	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics) THREE POLE 100Amps 25kA.	Nos	3033.00	Rupees Three Thousand Thirty Three Only
12	18	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers.63Amps	Nos	175.50	Rupees One Hundred Seventy Five And Paise Fifty Only
13	6	Supplying and fixing electro mechanical timer (without contactor) using necessary bolts, nuts and washers etc.. Group A, PWD Elec SR 2006-07.	Nos	3150.00	Rupees Three Thousand One Hundred Fifty Only
14	4	Fabricating, supplying and erecting swaged tubular pole of height ...Mtr having three sections, and providing two coats of red oxide paint and finished with two coats of enameled paint of approved quality and colour and M.S. base plate of suitable size welded at the bottom of the pole(as per IS) and 40mm dia GI / flexible PVC pipe of 1 mtr length fitted to the heavy gauge polycarbonate control box including 5way connector of size 167x125x82mm for 7.5M pole/200x160x98mm for remaining length of pole with front opening cover, with locking arrangements and suitable capacity MCB / DP switch, The pole shall be erected in cement concrete work (1:2:4) including excavation and refilling of planting depth of the pole to the ground level and the coping CC shall be up to 0.6M above ground level as per IS 2713 - 7. Erection of heavy duty pole on Footpath / median. 9Mt (5Mt Hb, 165.1mm dia 4.85mm thick x2M Hm, 139.7mm dia 4.50mm thick x 2M Ht, 114.3mm dia 3.65mm thick) as per IS 410 SP 32	Nos	11250.00	Rupees Eleven Thousand Two Hundred Fifty Only
15	8	Supplying of LED Floodlight with W System Power consumption pressure die cast aluminum housing with powder coating with IP 65 protection. 1, 200-275V voltage with electronic Driver, PF>0.9, should meet ANSI 2G Vibration test, Compliance to UL/CE with Class I. System rating shall be 50K hrs. @ Lumen maintenance of 70%, system efficacy > 80lm/w. Over load & Short circuit protection ensures reliable operation in spite of problem in output side. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w at 1W & Fixture Efficiency >80lm/w with nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008. Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 5 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED manufacturer.LED Floodlight 90W		10984.50	Rupees Ten Thousand Nine Hundred Eighty Four And Paise Fifty Only
16	10	Painting of existing street light pole after scrapping the old paint and painted with suitable colour enamel/Silver paint including coping/footing of the pole Upto 5Mtr street light pole.	Nos	375.00	Rupees Three Hundred Seventy Five Only
	1	KSRB 4-1 .1: Providing and laying in position plain cement concrete of cum 5,004.00 mix 1 :2:4 with ope cement @ 240kgs, with 40mm and down size graded granite metal coarse aggregates @0.7B7Bcum and fine aggregates @ 0.459cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications Specification No. KBS 4.1, 4.2	Cumt	3753.00	Rupees Three Thousand Seven Hundred Fifty Three Only

I am prepared to take up the above work at rates quoted in the Schedule 'B'

For MEGHANA ELECTRICALS
Contractor 
Proprietor


EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone